



ESTIMATE

To: The city of marine on stcroix

New Construction
 Remodeling
 Finish Carpentry

DATE: 03/18/2024

Gabe Saloka
 G&S Construction, LLC
 License# BC692446
 (651)-442-7542
 g.sconstruction@ymail.com

JOB	PAYMENT TERMS
Portico railing replacement	TBD

DESCRIPTION	LINE TOTAL
Replace roof rail system with custom milled African mahogany to match existing with half newel against building.	
3 coat combination paint primer sherwin williams duration	
Install treated blocks and galvanized brackets to roof to support newel post	
Railing will be assembled on site .All cuts will be sealed prior to install.	\$12,553.00
Railing system without half newel against building.End rail into existing embedded block on building	\$12,200.00
*The railing profile on the lower shoe rail will be slightly changed with a beveled top to shed water .The existing design was holding water and causing the rot to the lower rail. I do not believe the new design will be aesthetically noticeable but will be much better at preventing water damage	
TOTAL	

Note: Prices are based on current lumber costs

THANK YOU FOR YOUR BUSINESS!